



GENERAL NOTES:

1. ALL HYDRANT METER INSTALLATIONS SHALL INCLUDE APPROVED BACKFLOW PROTECTION.
2. THE CUSTOMER IS RESPONSIBLE FOR PROVIDING, INSTALLING, AND MAINTAINING ALL REQUIRED BACKFLOW PREVENTION EQUIPMENT DOWNSTREAM OF THE HYDRANT METER.
3. A REDUCED PRESSURE PRINCIPLE (RP) BACKFLOW PREVENTION ASSEMBLY SHALL BE INSTALLED DOWNSTREAM OF THE HYDRANT METER UNLESS AN APPROVED AIR GAP IS AUTHORIZED BY GSWC.
4. ALL BACKFLOW PREVENTION ASSEMBLIES MUST BE LISTED ON THE USC FOUNDATION FOR CROSS-CONNECTION CONTROL AND HYDRAULIC RESEARCH LIST OF APPROVED BACKFLOW PREVENTION ASSEMBLIES.
5. THE BACKFLOW ASSEMBLY SHALL BE INSTALLED IN ACCORDANCE WITH THIS DRAWING AND ALL APPLICABLE STATE OF CALIFORNIA REQUIREMENTS.
6. THE BACKFLOW ASSEMBLY MUST BE TESTED BY A STATE-CERTIFIED BACKFLOW TESTER WITHIN FIVE (5) DAYS OF THE HYDRANT METER BEING RELEASED TO CUSTOMER.
7. A COMPLETED BACKFLOW TEST REPORT SHALL BE EMAILED TO BACKFLOWTEST@GSWATER.COM WITHIN FIVE (5) DAYS OF METER BEING RELEASED. IF AN AIR-GAP IS APPROVED IN LIEU OF THE BACKFLOW PREVENTION ASSEMBLY, PHOTOS OF THE INSTALLED AIR GAP MUST BE SUBMITTED TO THE SAME EMAIL WITHIN FIVE (5) DAYS.
8. FAILURE TO SUBMIT THE REQUIRED DOCUMENTATION WITHIN THE REQUIRED TIME FRAME WILL RESULT IN TERMINATION OF WATER SERVICE.
9. ONGOING BACKFLOW TESTING SHALL BE PERFORMED QUARTERLY OR AS OTHERWISE REQUIRED BY GSW.
10. GSW RESERVES THE RIGHT TO INSPECT ALL INSTALLATIONS AND REQUIRE CORRECTION OF ANY NON-COMPLIANT CONDITION.

STANDARD FIRE HYDRANT METER INSTALLATION DETAILS

REVISED 1/12/2026

GOLDEN STATE WATER COMPANY

